



भा.कृ.अनु.प – केंद्रीय द्वीपीय कृषि अनुसंधान संस्थान
ICAR – CENTRAL ISLAND AGRICULTURAL RESEARCH INSTITUTE
बाथूबस्ती, गाराचरमाडाकघर, श्री विजयपुरम – 744105
Bathu Basti, Garacharma P.O, Sri Vijaya Puram – 744105
Phone: 03192 – 250436; 250235
Email: hoa.ciari@nic.in, director.ciari@icar.org.in, Website: <http://ciari.res.in>

F. No. 1-1/KVK-Nimbudera/Misc./2024-25

Date: 10.03.2026

NOTICE INVITING TENDER (OFFLINE MODE)

NAME OF THE WORK: Low cost Tin shed cum Duckery Farm under IFS Model at KVK, Nimbudera.

CRITICAL DATE SHEET

| | |
|---|---|
| Tender Reference No. | 1-1/KVK-Nimbudera/Misc./2024-25 |
| Estimated cost of work | Rs. 2,48,585/- |
| Last Date & Time of Tender / Bid submission | 16.03.2026 at 03.00 PM |
| Date & Time of Tender / Bid Opening | 16.03.2026 at 03:30 PM |
| Address of Communication | The Director, ICAR-CIARI, Sri Vijaya Puram |
| Place of Bid Submission | Reception, Administrative Block – II, ICAR-CIARI, Bathu Basthi, Sri Vijaya Puram – 744 105 |
| Place of Bid Opening | Administrative Officer Chamber, Administrative Block – II, ICAR-CIARI, Bathu Basthi, Sri Vijaya Puram – 744 105 |

Prakash Mondal
10.03.2026

(Prakash Mondal)

Assistant Administrative Officer
ICAR-Central Island
Agricultural Research Institute
Fort Blair - 744 105

Copy to:

1. Dr. Manoj Kumar, SMS (Agril. Engg.), ICAR-KVK, Nimbudera, N&M Andaman.
2. Dr. Y. Ramakrishna, Pr. Scientist & Head, ICAR-KVK, Nimbudera, N&M Andaman.
3. PS to Director, ICAR-CIARI, Sri Vijaya Puram, please for information of the Director.

ICAR-CENTRAL ISLAND AGRICULTURE RESEARCH INSTITUTE
SRI VIJAYA PURAM – 744 105

F. No. 1-1/KVK-Nimbudera/Misc./2024-25

Date: 10.03.2026

To

TENDER DOCUMENT

Name of Work: Low cost Tin shed cum Duckery Farm under IFS Model at KVK, Nimbudera.

| Sl. No. | Description of item | Qty. | Unit | Rate | Amount |
|---------|--|------|------|------|--------|
| 1. | Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m. (7m X 5m) | | | | |
| 1.1 | 2.28.1:- All kinds of soil | 35 | Sqm | | |
| 2. | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (10m X 6m X 0.15m) | | | | |
| 2.1 | 2.8.1:- All kinds of soil. | 3 | Cum | | |
| 3. | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : | | | | |
| 3.1 | a) 4.1.8:-1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) (7mX5mX0.10m) | 3.5 | Cum | | |
| 3.2 | b) 4.1.2:- 1:1½:3 (1 Cement: 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size) (7mX5mX0.12m) | 4.2 | Cum | | |
| 4. | Centering and shuttering including strutting, propping etc. and removal of form work for : | | | | |
| 4.1 | 4.3.1:- Foundations, footings, bases for columns | 3.4 | Sqm | | |
| 5. | Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. 10.26.3 Electric resistance or induction butt welded tubes | 290 | Kg | | |
| 6. | Providing and fixing bolts including nuts and washers complete. | 12 | Kg | | |

| | | | | | |
|---------|--|----|-------|-------|-------|
| 7. | Painting with black anti-corrosive bitumastic paint of approved brand and manufacture to give an even shade : 13.65.1 : Two or more coats on new work | 18 | Sqm | | |
| 8. | Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self-drilling /self-tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. | 48 | Sqm | | |
| 9. | Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. 16.70.2 Made of G.I. wire of dia. 4 mm, PVC coated to achieve outer dia not less than 5 mm in required colour and shade | 72 | Sqm | | |
| 10. | PVC mesh 1/8 inch/ GI mesh 1/8 Inch as as required complete as per the direction of Engineer-in-charge. | 76 | Sqm | | |
| 11. | Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self-drilling/ self-tapping screws complete : 12.51.1 Ridges plain (500 - 600mm | 6 | Meter | | |
| | | | | Total | ₹ |
| (Rupees | | | | | Only) |

TERMS & CONDITIONS:

- 1) The envelope containing tender document should be neatly super scribed with the name of the work, reference no., closing date failing which the tender will be returned without opening.
- 2) The contractor should mention the correct postal address and contact no. in the space provided in the agreement. If there is any change in the postal address/ contact no., the contractor should inform to the office in writing immediately about the change. Institute shall not be responsible for non-receipt of document due to postal delay/ undelivered/ non-recipient at your end.

- 3) The contractor may quote the rate after inspection of site and clarification of all details of the tender document from Dr. Manoj Kumar, SMS (Agril. Engg.), ICAR-KVK, Nimbudera, N&M Andaman.
- 4) Incomplete or conditional quotations shall be rejected.
- 5) No Splitting of procurement: The procurement entity shall not split or divide the procurement requirement into multiple smaller contracts with the intention of bringing the value within the quotation limit prescribed for such procurement.
- 6) The quoted prices must include all applicable components such as transportation charges, insurance, duties, taxes and any other incidental expenses, so that the comparison of quotations is made on a comprehensive price basis.
- 7) Single Quotation Rule: Each Contractor/supplier shall be permitted to submit only one quotation against the requirement and no modification or alteration of quotation shall be allowed after submission.
- 8) Work shall be carried out as per the instruction, direction and satisfaction of Dr. Manoj Kumar, SMS (Agril. Engg.), ICAR-KVK, Nimbudera, N&M Andaman.
- 9) The rate should include all labours and material charges, transportation, tools and tackles etc. as required for completing the work.
- 10) The work should be started immediately from the date of issue of work order failing which the work order shall be cancelled and the performance guarantee will be forfeited on the recommendation of Dr. Manoj Kumar, SMS (Agril. Engg.), ICAR-KVK, Nimbudera, N&M Andaman.
- 11) The work should be completed within 12 (Twelve) days from the date of issue of work order. The contractor may also request for extension of period of completion with valid reasons for acceptance of Competent Authority, ICAR-CIARI, Sri Vijaya Puram.
- 12) The Director shall have the liberty to postpone or not to execute any item of work and the contractor shall not be entitled to any compensation for non-execution of such items of work.
- 13) During execution no change shall be made by the contractor in the approved specifications at site without the consent of the Dr. Manoj Kumar, SMS (Agril. Engg.), ICAR-KVK, Nimbudera, N&M Andaman.
- 14) All the materials purchased for construction/ painting etc. by the contractor shall be as per the CPWD/ ISI/ BIS Standards/ specification and got approved by the Dr. Manoj Kumar, SMS (Agril. Engg.), ICAR-KVK, Nimbudera, N&M Andaman.
- 15) The inferior quality or rejected materials are to be removed immediately from the site failing which the same will get removed by the Institute and the expense involved will be deducted from the contractor's bill.
- 16) The water as required for construction and curing shall be arranged by the contractor for which no extra payment shall be made.
- 17) The contractor shall not be provided any store for storing of the construction materials and their tools. However, a site will be given temporarily to construct a store in ICAR-KVK, Nimbudera, N&M Andaman.. The store should be dismantled immediately after handing over the structure/ buildings to the Institute failing which the bill will not be processed for release of payment.
- 18) In case the contractor fails to complete the work within the stipulated/ extended period of time and according to our satisfaction, the Director, ICAR-Central Island Agricultural Research Institute shall have the right to terminate the contract and get the work done through any other firm or agency.
- 19) Quantity of work may be increased or decreased according to the actual need of work and hence minor deviation of work shall be undertaken as per quoted rate without asking any compensation.
- 20) The contractor has to deposit 3% of the contract value in the form of Demand Draft/Bank Guarantee/ Fixed deposit in favour of "ICAR Unit, CARI, Sri Vijaya Puram" as Performance Guarantee for the contract against acceptance of tender and the same shall be kept as security deposit and shall be released after one year of successful completion of the work.
- 21) If the contractor fails to deposit 3% Performance Security within 02 (Two) days from the issue of acceptance letter, the tender may be cancelled and the Contractor may not be allowed to participate any tender of the Institute in future.
- 22) The contractor has to pay minimum wages to their labour force engaged for the civil work as per A&N Administration notification issued from time to time. The contractor shall be

- bound by all provisions of contract labour (Regulation and Abolition) Act 1970 and Central Rules 1971.
- 23) The standard deduction such as Income Tax and other taxes as applicable shall be deducted from the bill of the contractor.
 - 24) After completion of the work within one year, if any defect, or damage or poor workmanship is noticed, the same shall be rectified by the contractor, within 10 days failing which the Security Deposit shall be forfeited.
 - 25) After completion of work, the left over material at the site, if any, shall be removed within seven days failing which the material shall be removed at the cost and risk of the contractor by the Institute.
 - 26) The Director, ICAR-CIARI, Sri Vijaya Puram also reserves the right to cancel the work, after award of work due to some administrative/ technical reasons.
 - 27) The Director, ICAR-CIARI, Sri Vijaya Puram shall be the sole arbitrator for all disputes between the contractor and Institute. The decision of the Director shall be final and binding to both the parties.

Prakash Mondal
90.03.2016

(Prakash Mondal)

Assistant Administrative Officer
Asst. Administrative Officer
ICAR-Central Island
Cultural Research Institute
Fort Blair - 744 105

Signature of the Contractor
Name & complete postal address
With telephone no., date and seal